

**MEMORANDUM**

To: All Interested Vendors

From: Theresa A. Kauffman  
IT Vendor and Procurement Administrator

Date: December 9, 2022

Subject: Addendum No. 3  
RFP 22-047 Reynoldsburg Technology Cabling  
**Pre-Bid Meeting Questions**

---

The following questions were asked during the pre-bid meeting on November 30, 2022

Project Name: CML Reynoldsburg Branch  
 Structured Cabling Phase 7 eRate 22-047  
 Address: 1402 Brice Road Columbus, OH 43068

Owner: Columbus Metropolitan Library  
 Architect: JBAD / Gund Partnership  
 Turner Construction Project Number 220871



Question #	Drawing / Spec Section #	Date Initiated	Question / Clarification Request	Response	Date Answered	Distributed to Bidders
1	SOW	11/30/22	Are we to bid racks?	Yes. Please reference sheet T5.01 and specs 271116, 271123, 271126 for project specific requirements	12/08/22	Addendum #3
2	SOW	11/30/22	Who is conduit run by?	Electrician. Electrician provides cable trays as well.	12/08/22	Addendum #3
3	SOW	11/30/22	Will the penetrations for cameras be done by others?	Yes.	12/08/22	Addendum #3
4	n/a	11/30/22	Should ceiling jacks terminated to a biscuit?	Yes, provide biscuit jacks/surface blocks for all ceiling mounted data. Please provide product data cut sheets for blocks with submittals.	12/08/22	Addendum #3
5	T1.01	11/30/22	Regarding the camera in the elevators, how are terminations to occur?	This cabling contractor will be required to terminate cabling via the wire bundle at the car top and inside of the elevator controller where terminations will be made. The elevator contractor will assist with access.	12/08/22	Addendum #3
6		12/07/22	The plans and addendum #2 mention a backbone diagram to explain fiber counts, but I cannot find this sheet on either the Addendum #2 or the drawings, is this diagram in an available location at the moment?			
7	SOW	12/07/22	I see the Access control is using #18 Gauge shielded + other cabling not involving Category Cable, are we also running and terminating these runs?	No, access control #18 Gauge shielded wiring is not part of this scope at this time. Please reference the scope of work for cabling included and excluded from this contract.	12/08/22	Addendum #3
8	SOW	12/07/22	Which of us would be providing the floor boxes that need data hookup?	If a floor box has power AND data required, Div 26 Electrical will provide. If there are any floor boxes with data ONLY, this structured cabling contractor should provide.	12/08/22	Addendum #3
9	SOW	12/07/22	Are we Furnishing & Installing the 4 post racks?	Yes	12/08/22	Addendum #3
10	spec 270553	12/07/22	Is there a preferred color of cable per discipline (i.e Green = WAP's, Blue = Data, Yellow = Surveillance, etc.)	Network Team prefers all white cable	12/08/22	Addendum #3
11	SOW	12/07/22	Are we furnishing & Installing the Telecom Bus Bars for grounding?	Yes	12/08/22	Addendum #3

**BIDDERS ARE REQUIRED TO ACKNOWLEDGE THE RECEIPT OF THIS MEMORANDUM (ADDENDUM NO. 3) ON THE ACKNOWLEDGEMENT OF ADDENDA FORM IN THE RFP DOCUMENTS**